

## KALBURGI CEMENT PVT. LTD.



Corporate Office: 8-2-626, Reliance Majestic Building, Road No. 10, Banjara Hills, Hyderabad – 500 034, A.P., India. Ph.: +91 40 3006999; Fax: +91 40 3006955 Works: Chatrasala (V), Kharchkhed (Post) - 585 320, Chincholi (Tq.), Gulbarga Dist.; Ph. +91 08472 305999; Fax: +91 08472 305999

## TEST CERTIFICATE VICAT-DURAMATE



Week No: 1

## **PPC GRADE**

Despatched from: 01.01.2019 TO 06.01.2019

Despatched if oil. 01.01.2019 10 00.01.2019			week no: 1	
A. PHYSICAL REQUIREMENTS		RESULTS	As per IS 1489 (Part-1) 2015	
Finene	ss:			
a.	Specific Surface (m2/kg)	346	Not less than 300	
b.	Normal Consistency (%)	32.50		
Soundness:				
a.	By Le-Chatelier Method (mm)	0.50	Not more than 10 mm	
b.	By Autoclave (%)	0.034	Not more than 0.8 %	
Setting Time:				
a.	Initial Setting Time (minutes)	165	Not less than 30	
b.	Final Setting Time (minutes)	260	Not more than 600	
Compressive Strength (MPa)				
a.	3 days	26.89	Not less than 16	
b.	7 days	Awaited	Not less than 22	
c.	28 days	Awaited	Not less than 33	
d.	Drying Shrinkage(%)	Awaited	Not more than 0.15	
e.	Flyash Addition (%)	33.58	Not more than 35	
B. CHEMICAL REQUIREMENTS				
a.	Insoluble Residue (%)	30.22	X+4(100-X)/100; X = % of Flyash	
b.	Magnesia (%)	0.89	Not more than 6.0	
c.	Sulphuric Anhydride (%)	1.90	Not more than 3.5	
d.	Loss on Ignition (%)	2.44	Not more than 5.0	
e.	Alkali Content (%)	0.63	Not more than 0.90	
f.	Temperature During Testing( <sup>o</sup> C)	26.50	27 ± 2	

17. of:12

Section In-Charge (Q.C)

HOD (Q.C)