

## **KALBURGI CEMENT PVT. LTD.**

Corporate Office: 8-2-626, Reliance Majestic Building, Road No. 10, Banjara Hills, Hyderabad – 500 034, A.P., India. Ph.: +91 40 3006999; Fax: +91 40 30006955

TRUST. LEGACY. FOREVER.

Works : Chatrasala (V), Kharchkhed (Post) - 585 320, Chincholi (Tq.), Gulbarga Dist.

## **TEST CERTIFICATE (PPC)**

## **Product : VICAT - DURAMATE**

## Despatched from: 14.01.2019 to 20.01.2019

A. PHYSICAL REQUIREMENTS		RESULTS	As per IS 1489 (Part-1) 2015
Finenes	SS:		
a.	Specific Surface (m2/kg)	349	Not less than 300
b.	Normal Consistency (%)	32.50	
Soundness:			
a.	By Le-Chatelier Method (mm)	0.50	Not more than 10 mm
b.	By Autoclave (%)	0.032	Not more than 0.8 %
Setting Time:			
a.	Initial Setting Time (minutes)	165	Not less than 30
b.	Final Setting Time (minutes)	270	Not more than 600
Compressive Strength (MPa)			
a.	3 days	28.08	Not less than 16
b.	7 days	37.50	Not less than 22
c.	28 days	55.36	Not less than 33
d.	Drying Shrinkage(%)	Awaited	Not more than 0.15
e.	Flyash Addition (%)	33.16	Not more than 35
B. CHEMICAL REQUIREMENTS			
a.	Insoluble Residue (%)	29.84	X+4(100-X)/100; X = % of Flyash
b.	Magnesia (%)	0.95	Not more than 6.0
c.	Sulphuric Anhydride (%)	1.96	Not more than 3.5
d.	Loss on Ignition (%)	2.74	Not more than 5.0
e.	Alkali Content (%)	0.72	Not more than 0.90
f.	Temperature During Testing( <sup>O</sup> C)	27.00	27 ± 2



Section In-Charge (Q.C)





3

Week No: