



JK LAKSHMI

$CEMENT\ Ltd.$

JAYKAYPURAM—307019 Dist. Sirohi, Rajasthan TEST CERTIFICATE FOR PORTLAND POZZOLANA CEMENT



LICENCE NO. CM/L-1234838

TC-5708

 ${\bf ULR\ NO.\ TC\text{-}570819000000000131F}$

WEEK No.	33	DATE OF ISSUE 27.08.2019		

WEEK No. 33		DATE OF ISSU	JE 27.08.2019
CHEMICAL / PHYSICAL REQUIREMENTS	SPECIFICATION CLAUSE No.	REQUIREMENT AS PER IS No.1489(PART-I) – 2015	RESULTS OBTAINED
CHEMICAL REQUIREMENTS:	6		
(i) Loss on ignition, percent by mass, Max.	6.1	5.0	2.76
(ii) Magnesia, percentage by mass, Max	6.1	6.0	2.40
(iii) Sulphuric Anhydride (SO ₃), percent by mass, Max	6.1	3.5	2.56
(iv) Insoluble Residue, percent by mass Max.	6.1	4(100-x) x+ 100 (x=where x is the declare % age of Fly Ash)	23.41
(v) Insoluble Residue, percent by mass Min	6.1	0.6 x	15.0
(vi) Declared % of Fly Ash	5 & 9.1	Not less than 15% and Not more than 35%	28+/-3
(vii) Chloride, percent by mass	9.2	Not more than 0.1	0.065
PHYSICAL REQUIREMENTS:	7		
(i) FINENESS : SP. SURFACE	7.1	Not less than 300 m2/kg	348
(ii) SOUNDNESS: a) Le-chatelier method Expansion	7.2	Not more than 10 mm	1.00
b) Auto clave test expansion		Not more than 0.8%	0.059
(iii) SETTING TIME a) Initial Setting time in Minutes	7.3	30 minutes, minimum	135
b) Final setting time in Minutes		600 minutes, maximum	175
(iv) COMPRESIVE STRENGTH 72 ± 1 Hours (3 Days)	7.4	16 Mpa, Min	28.0
168 ± 2 Hours (7 Days)		22 Mpa, Min	38.0
672 ± 4 Hours (28 Days) (v) Drying Shrinkage	7.5	33 Mpa, Min Not be more than 0.15%	Under Testing Under Testing

REMARKS: The test results complies with the requirements of IS: 1489(Part-I): 2015 for all Chemical requirements and Physical requirements including Compressive Strength up to 7-days.

Note: Results reported above are the average test results of all samples testing during relevant week.

CERTIFIED
ISO 9001:2015
ISO 14001:2015
OHSAS 18001:2007

Share

HOD(QC)

