

KALBURGI CEMENT PVT. LTD.

Corporate Office: 8-2-626, Reliance Majestic Building, Road No. 10, Banjara Hills, Hyderabad – 500 034, A.P., India. Ph.: +91 40 3006999; Fax: +91 40 30006955

Works : Chatrasala (V), Kharchkhed (Post) - 585 320, Chincholi (Tq.), Gulbarga Dist.

TEST CERTIFICATE (PPC)

Product : VICAT - DURAMATE

Week No:

Despatched from: 16.03.2020 to 22.03.2020

A. PHYSICAL REQUIREMENTS		RESULTS	As per IS 1489 (Part-1) 2015
Finenes	ss:		
a.	Specific Surface (m2/kg)	346	Not less than 300
b.	Normal Consistency (%)	32.50	
Soundness:			
a.	By Le-Chatelier Method (mm)	0.50	Not more than 10 mm
b.	By Autoclave (%)	0.048	Not more than 0.8 %
Setting Time:			
a.	Initial Setting Time (minutes)	175	Not less than 30
b.	Final Setting Time (minutes)	285	Not more than 600
Compressive Strength (MPa)			
a.	3 days	26.74	Not less than 16
b.	7 days	36.44	Not less than 22
c.	28 days	55.69	Not less than 33
d.	Drying Shrinkage(%)	Awaited	Not more than 0.15
e.	Flyash Addition (%)	30.91	Not more than 35
B. CHEMICAL REQUIREMENTS			
a.	Insoluble Residue (%)	27.82	X+4(100-X)/100; X = % of Flyash
b.	Magnesia (%)	1.02	Not more than 6.0
c.	Sulphuric Anhydride (%)	2.32	Not more than 3.5
d.	Loss on Ignition (%)	2.44	Not more than 5.0
e.	Alkali Content (%)	0.56	Not more than 0.90
f.	Temperature During Testing(^O C)	27.50	27 ± 2

TI. fry

Section In-Charge (Q.C)

Authorised Signature



12