Bureau Veritas (India) Private Limited **Construction Services Laboratory** Plot No. B3/B4, TTC Industrial Area Off Thane-Belapur Road, M.I.D.C. Digha, Navi Mumbai - 400 708. INDIA

Tel.: +91 22 50954870

Email: sales.mum@bureauveritas.com / adminlab.mum@bureauveritas.com







## **TEST REPORT**

Report No.: MUM/2128/3/2023/7-871-1

Date of Receipt: 18.03.2023

Date: 23.03.2023 Page: 1 of 2

ULR-TC549123100003654F

#### RECONS BUILDING PRODUCTS PVT. LTD.

1-A, 5<sup>TH</sup> Floor, Times Square, Andheri Kurla road, Marol Mumbai Suburban, Maharashtra, 400059

**MECHANICAL TESTING Buildings Materials** 

## **TEST REPORT**

Source of Sample

Sample supplied by the customer.

Number of Sample Tested

24 (Tweenty four only)

Condition of Sample

Satisfactory

Customer's Reference

Letter dt. 18.03.2023

Lab Reference Number

2023/MAR/2308379

Product

Autoclaved Cellular (Aerated) Concrete Block

Size\*

600 x 200 x 100 mm

Brand Name\*

NOVA

Period of test

18.03.2023 to 23.03.2023

Test Method

IS: 2185 (PART 3)-1984 RA-2020, IS: 6441 (Part 1 & 5) RA-2022

# 1. Compressive Strength:

SI. No.	Dimension (mm)	Moisture content before Compressive Strength (%)	Avg. Moisture content before Compressive Strength (%)	Cross Sectional Area (mm²)	Load (kN)	Compressive Strength (N/mm²) (X-0.6R)	Avg. Compressive Strength (N/mm²)
1	150.2 x 150.1 x 150.1	10.19		22540	102	4.4	
2	150.0 x 150.0 x 150.1	10.37	0.70	22500	97	4.3	
3	150.1 x 150.0 x 150.1	9.61		22515	100	4.4	
4	150.1 x 150.0 x 150.1	9.85		22515	104	4.6	
5	150.0 x 150.1 x 150.0	10.06		22515	88	3.9	
6	150.1 x 150.1 x 150.1	9.78		22525	95	4.2	4.3
7	150.1 x 150.1 x 150.1	9.38	9.79	22530	98	4.3	4.2
8	150.1 x 150.1 x 150.1	9.46		22525	110	4.8	
9	150.1 x 150.1 x 150.1	9.64		22525	88	3.8	
10	150.1 x 150.1 x 150.1	9.58		22525	87	3.8	
11	150.1 x 150.1 x 150.1	9.80		22525	86	3.7	
12	150.1 x 150.1 x 150.1	9.70		22525	94	4.1	

<sup>\*</sup>Indicates information supplied by the customer for which the laboratory has no control. Sampling not done by laboratory, results relate to the sample tested only. The contents of the report shall not be reproduced either in full or in part without prior written consent of the issuing authority. All services are rendered in accordance with Bureau Veritas General conditions of service.

Kindly refer to the T&C at www.bureauveritas.co.in – General Terms & Conditions – General terms & Conditions-BVIL
Regd. Office: 72, Business Park, Ground Floor, Marol Industrial Area, MIDC, Cross Road 'C', Andheri (East), Mumbai - 400 093, INDIA • www.bureauveritas.co.in

Bureau Veritas (India) Private Limited Construction Services Laboratory Plot No. B3/B4, TTC Industrial Area Off Thane-Belapur Road, M.I.D.C. Digha, Navi Mumbai - 400 708. INDIA

Tel.: +91 22 50954870

Email: sales.mum@bureauveritas.com / adminlab.mum@bureauveritas.com







**TEST REPORT** 

Report No.: MUM/2128/3/2023/7-871-1

Date of Receipt: 18.03.2023

Date: 23.03.2023

Page: 2 of 2

ULR-TC549123100003654F

## 2. Block Density:

Sl.No.	Dimension (mm)	Block Density (kg/m³)	Avg. Block Density (kg/m³)	Limits as Per IS-2185 (PART 3) -1984 RA 2020
1	200 x 101 x 51	563.0		
2	200 x 100 x 51	562.7	560.6	451-1000 (kg/m³)
3	200 x 101 x 51	556.2		

## PHYSICAL REQUIREMENT: AS PER IS-2185 (PART 3) -1984 RA 2020

SI. No.	Density (kg/m³)	Minimum Average Compressive Strength of 12 Units (N/mm²)			
		Grade-1	Grade-2		
1	451 to 550	2.0	1.5		
2	551 to 650	4.0	3.0		
3	651 to 750	5.0	4.0		
4	751 to 850	6.0	5.0		
5	851 to 1000	7.0	6.0		

Remark- The tested sample confirms to IS 2185 (Part 3)-1984 RA 2020 Grade I (density of 551-650 kg/m³) for the tested parameter.

\*END OF REPORT\*

For BUREAU VERITAS (INDIA) PVT LTD. **Construction Services Laboratory** 



Bureau Veritas (India) Private Limited Construction Services Laboratory Plot No. B3/B4, TTC Industrial Area

Off Thane-Belapur Road, M.I.D.C. Digha, Navi Mumbai - 400 708. INDIA

Tel.: +91 22 50954870 Email: sales.mum@bureauveritas.com / adminlab.mum@bureauveritas.com







TC-5491

### **TEST REPORT**

Report No.: MUM/2128/3/2023/7-871-2

Date of Receipt: 18.03.2023

Date: 23.03.2023 Page: 1 of 2

ULR-TC549123100003655F

#### RECONS BUILDING PRODUCTS PVT. LTD.

1-A, 5<sup>TH</sup> Floor, Times Square, Andheri Kurla road, Marol Mumbai Suburban, Maharashtra, 400059

**MECHANICAL TESTING Buildings Materials** 

**TEST REPORT** 

Source of Sample

Sample supplied by the customer.

Number of Sample Tested

15 (Fifteen only)

Condition of Sample

Satisfactory

Customer's Reference

Letter dt. 18.03.2023

Lab Reference Number

2023/MAR/2308379

Product

Autoclaved Cellular (Aerated) Concrete Blocks

Size\*

600 x 200 x 150 mm

**Brand Name\*** 

NOVA

3

Period of test

18.03.2023 to 23.03.2023

Test Method

IS: 2185 (PART 3)-1984 RA-2020, IS: 6441 (Part 1 & 5) RA-2022

#### 1. Compressive Strength:

SI. No.	Average Dimension (mm)	Moisture content before Compressive Strength (%)	Avg. Moisture content before Compressive Strength (%)	Cross Sectional Area (mm²)	Load (kN)	Compressive Strength (N/mm²) (X-0.6R)	Avg. Compressive Strength (N/mm²)
1	150.2 x 150.1 x 150.1	10.04		22545	102	4.5	
2	150.0 x 150.1 x 150.1	10.55		22510	96	4.2	
3	150.1 x 150.1 x 150.1	10.67		22520	83	4.1	
4	150.1 x 150.1 x 150.1	10.30		22530	105	4.6	
5	150.0 x 150.0 x 150.0	10.57		22500	95	4.2	
6	150.1 x 150.1 x 150.1	10.25		22530	98	4.2	4.4
7	150.1 x 150.1 x 150.1	10.55	10.44	22520	106	4.7	4.4
8	150.2 x 150.1 x 150.2	10.27		22535	95	4.2	
9	150.1 x 150.2 x 150.1	10.67		22535	92	4.0	
10	150.1 x 150.1 x 150.1	10.81		22525	105	4.6	
11	150.2 x 150.1 x 150.2	10.23		22540	107	4.7	
12	150.1 x 150.2 x 150.1	10.39		22540	104	4.6	

# Bureau Veritas (India) Private Limited Construction Services Laboratory

Plot No. B3/B4, TTC Industrial Area Off Thane-Belapur Road, M.I.D.C. Digha, Navi Mumbai - 400 708. INDIA

Tel.: +91 22 50954870

Email: sales.mum@bureauveritas.com / adminlab.mum@bureauveritas.com







### **TEST REPORT**

Date: 23.03.2023

Page: 2 of 2

ULR-TC549123100003655F

# Report No.: MUM/2128/3/2023/7-871-2

Date of Receipt: 18.03.2023

2. Block Donaites

2. Block Delisity.						
Si.No.	Dimension (mm)	Block Density (kg/m³)	Avg. Block Density (kg/m³)	Limits as Per IS-2185 (PART 3) -1984 RA 2020		
1	200 x 101 x 51	599.9				
2	200 x 100 x 51	608.8	598.7	451-1000 (kg/m³)		
3	200 x 101 x 51	587.3				

# PHYSICAL REQUIREMENT: AS PER IS-2185 (PART 3) -1984 RA 2020

SI.	Density (kg/m³)	Minimum Average Compressive Strength of 12 Units (N/mm²)			
1407		Grade-1	Grade-2		
1	451 to 550	2.0	1.5		
2	551 to 650	4.0	3.0		
3	651 to 750	5.0	4.0		
4	751 to 850	6.0	5.0		
5	851 to 1000	7.0	6.0		

Remark- The tested sample confirms to IS 2185 (Part 3)-1984 RA 2020 Grade I (density of 551-650 kg/m³) for the tested parameter.

\*END OF REPORT\*

For BUREAU VERITAS (INDIA) PVT LTD. **Construction Services Laboratory** 

> ab Engineer **Authorised Signatory**

Gayatri Bawane

Bureau Veritas (India) Private Limited Construction Services Laboratory Plot No. B3/B4, TTC Industrial Area Off Thane-Belapur Road, M.I.D.C.

Digha, Navi Mumbai - 400 708. INDIA Tel.: +91 22 50954870

Email: sales.mum@bureauveritas.com / adminlab.mum@bureauveritas.com

#### **TEST REPORT**



Report No.: MUM/2128/3/2023/7-872-1

Date of Receipt: 18.03.2023

Date: 23.03.2023

Page: 1 of 1

# RECONS BUILDING PRODUCTS PVT. LTD.

1-A, 5<sup>TH</sup> Floor, Times Square, Andheri Kurla road, Marol Mumbai Suburban, Maharashtra, 400059

**TEST REPORT** 

Source of Sample

Sample supplied by the customer.

Number of Sample Tested

03 (Three only)

Condition of Sample

Satisfactory

Customer's Reference

Letter dt. 18.03.2023

Lab Reference Number

2023/MAR/2308379

Product

Autoclaved Cellular (Aerated) Concrete Block

Size\*

600 x 200 x 100 mm

**Brand Name\*** 

NOVA

Period of test

18.03.2023 to 21.03.2023

Test Method

As per customer requirement

## Results:

SI. No.	Test Performed	Results (%)
1	Water Absorption	37.8

\*END OF REPORT\*

For BUREAU VERITAS (INDIA) PVT LTD. **Construction Services Laboratory** 

> Gayatri Bawane Lab Engineer **Authorised Signatory**

<sup>\*</sup>Indicates information supplied by the customer for which the laboratory has no control. Sampling not done by laboratory, results relate to the sample tested only. The contents of the report shall not be reproduced either in full or in part without prior written consent of the issuing authority. All services are rendered in accordance with Bureau Veritas General conditions of service.

Bureau Veritas (India) Private Limited Construction Services Laboratory

Plot No. B3/B4, TTC Industrial Area Off Thane-Belapur Road, M.I.D.C. Digha, Navi Mumbai - 400 708. INDIA

Tel.: +91 22 50954870 Email: sales.mum@bureauveritas.com / adminlab.mum@bureauveritas.com

#### **TEST REPORT**



Report No.: MUM/2128/3/2023/7-872-2

Date of Receipt: 18.03.2023

Date: 23.03.2023

Page: 1 of 1

# RECONS BUILDING PRODUCTS PVT. LTD.

1-A, 5<sup>TH</sup> Floor, Times Square, Andheri Kurla road, Marol Mumbai Suburban, Maharashtra, 400059

## **TEST REPORT**

Source of Sample

Sample supplied by the customer.

**Number of Sample Tested** 

03 (Three only)

Condition of Sample

Satisfactory

Customer's Reference

Letter dt.18.03.2023

Lab Reference Number

2023/MAR/2308379

Product

Autoclaved Cellular (Aerated) Concrete Blocks

Size\*

600 x 200 x 150 mm

**Brand Name\*** 

NOVA

Period of test

18.03.2023 to 21.03.2023

Test Method

As per customer requirement

# **Results:**

SI. No.	Test Performed	Results (%)
1	Water Absorption	36.2

\*END OF REPORT\*

For BUREAU VERITAS (INDIA) PVT LTD. **Construction Services Laboratory** 

