

Report No. MUM/2128/3/2023/5-585

Date of Receipt: 18.03.2025

Date: 17.04.2025

Page 1 of 1

**RECONS BUILDING PRODUCTS PVT.LTD.**

805-A, 8th Floor, 349 Business Park, Near Natraj Building,  
 Western Express Highway, Above ICICI Bank, Andheri East, Mumbai - 400069.

**FINAL TEST REPORT**

|                          |   |                                  |
|--------------------------|---|----------------------------------|
| Source of sample         | : | Sample supplied by the customer. |
| Number of samples tested | : | 01(One only).                    |
| Customer's Reference     | : | Letter Dt.: 18.03.2025           |
| Condition of sample      | : | Satisfactory                     |
| Product                  | : | Ready Mix Plaster                |
| Material Identification* | : | RECONS PLAST                     |
| Lab Reference Number     | : | 2023/MAR/2308379                 |
| Period of Test           | : | 17.04.2025 to 17.04.2025         |

**PHYSICAL PROPERTIES:**

| Sl. No. | Test Conducted                              | Results | Test Method      |
|---------|---|---------|------------------|
| 1       | Consistency (%)                             | 14.5    | ---              |
| 2       | Pot Life (Minutes)                          | 1:30    |                  |
| 3       | Initial Setting Time (Hours : Minutes)      | 4:30    | IS 4031 – Part 5 |
| 4       | Final Setting Time (Hours : Minutes)        | 5:30    |                  |
| 5       | Fresh Wet Density (kg/m <sup>3</sup> )      | 2080    | IS 2386 - Part 3 |
| 6       | Dry Loose Bulk Density (kg/m <sup>3</sup> ) | 1645    |                  |
| 7       | Compressive Strength (MPa)                  |         | ASTM C 109       |
| a       | 7 Days                                      | 5.16    |                  |
| b       | 28 Days                                     | 8.89    |                  |

**\*END OF REPORT\***

For Bureau Veritas (India) Pvt. Ltd.  
**Construction Services Laboratory**



Ravindra Ghatat  
 RGG  
 Lab Incharge - Cement  
 Authorised Signatory

