

## KALBURGI CEMENT PVT. LTD.

<u>Corporate Office</u>: 8-2-626, Reliance Majestic Building, Road No. 10, Banjara Hills, Hyderabad – 500 034, A.P., India. Ph.: +91 40 3006999; Fax: +91 40 30006955 IS:1489 (Part-1)

CM/L :4596685

25

Works :Chatrasala (V), Kharchkhed (Post) - 585 320, Chincholi (Tq.), Gulbarga Dist.

## TEST CERTIFICATE (PPC)

**Product : VICAT - DURAMATE** 

Week No:

Despatched From : 18/6/2025 TO 24/6/2025			
A. PHYSICAL REQUIREMENTS (as per IS:4031)		RESULTS	As per IS 1489 (Part-1) 2015
Fineness:			
a.	Specific Surface (m2/kg)	331	Not less than 300
b.	Normal Consistency (%)	31.50	
Soundness:			
a.	By Le-Chatelier Method (mm)	1.50	Not more than 10 mm
b.	By Autoclave (%)	0.05	Not more than 0.8 %
Setting Time:			
a.	Initial Setting Time (minutes)	160	Not less than 30
b.	Final Setting Time (minutes)	260	Not more than 600
Compressive Strength (MPa)			
a.	3 days	24.09	Not less than 16
b.	7 days	Awaited	Not less than 22
C.	28 days	Awaited	Not less than 33
d.	Drying Shrinkage(%)	Awaited	Not more than 0.15
e.	Flyash Addition (%)	29.11	Not more than 35
B. CHEMICAL REQUIREMENTS (as per IS:4032)			
			Max=(X+4*(100-X)/100)
a.	Insoluble Residue (%)	25.32	Min=0.6*X, X = Flyash addition (%)
b.	Magnesia (%)	1.30	Not more than 6.0
C.	Sulphuric Anhydride (%)	2.03	Not more than 3.5
d.	Loss on Ignition (%)	1.84	Not more than 5.0
e.	Alkali Content (%)	0.82	Not Specified
1			

27.50

f.

Temperature During Testing <sup>0</sup>C

Asst Manager-QC



27 ± 2