

## **KALBURGI CEMENT PVT. LTD.**

<u>Corporate Office</u>: 8-2-626, Reliance Majestic Building, Road No. 10, Banjara Hills, Hyderabad – 500 034, A.P., India. Ph.: +91 40 3006999; Fax: +91 40 30006955

Works : Chatrasala (V), Kharchkhed (Post) - 585 320, Chincholi (Tq.), Gulbarga Dist.



CM/L:4596685

## **TEST CERTIFICATE (PPC)**

Product: VICAT - DURAMATE Week No: 46

Despatched From: 12/11/2023 TO 18/11/2023

Despatched From . 12/11/2023 TO 16/11/2023			
A. PH	YSICAL REQUIREMENTS	RESULTS	As per IS 1489 (Part-1) 2015
Fineness:			
a.	Specific Surface (m2/kg)	327	Not less than 300
b.	Normal Consistency (%)	32.00	
Soundness:			
a.	By Le-Chatelier Method (mm)	1.00	Not more than 10 mm
b.	By Autoclave (%)	0.07	Not more than 0.8 %
Setting Time:			
a.	Initial Setting Time (minutes)	165	Not less than 30
b.	Final Setting Time (minutes)	270	Not more than 600
Compressive Strength (MPa)			
a.	3 days	24.15	Not less than 16
b.	7 days	Awaited	Not less than 22
C.	28 days	Awaited	Not less than 33
d.	Drying Shrinkage(%)	Awaited	Not more than 0.15
e.	Flyash Addition (%)	29.74	Not more than 35
B. CHEMICAL REQUIREMENTS			
а.	Insoluble Residue (%)	26.04	X+4(100-X)/100; X = % of Flyash
b.	Magnesia (%)	0.95	Not more than 6.0
C.	Sulphuric Anhydride (%)	2.32	Not more than 3.5
d.	Loss on Ignition (%)	1.69	Not more than 5.0
e.	Alkali Content (%)	0.71	Not more than 0.90
f.	Temperature During Testing <sup>0</sup> C	27.40	27 ± 2

P-Gas

HOD - OC

Dy Manager-QC