

KALBURGI CEMENT PVT. LTD.

Corporate Office: 8-2-626, Reliance Majestic Building, Road No. 10, Banjara Hills, Hyderabad – 500 034, A.P., India. Ph.: +91 40 3006999; Fax: +91 40 30006955

Works : Chatrasala (V), Kharchkhed (Post) - 585 320, Chincholi (Tq.), Gulbarga Dist.





CM/L:4596685

TEST CERTIFICATE (PPC)

Product: VICAT - DURAMATE Week No: 34

Despatched From: 20-08-2022 TO 26-08-2022

Despatched 110111. 20-00-2022 10 20-00-2022			
A. PH	YSICAL REQUIREMENTS	RESULTS	As per IS 1489 (Part-1) 2015
Finen	ess:		
a.	Specific Surface (m2/kg)	316	Not less than 300
b.	Normal Consistency (%)	32.5	
Soundness:			
a.	By Le-Chatelier Method (mm)	1.00	Not more than 10 mm
b.	By Autoclave (%)	0.03	Not more than 0.8 %
Setting Time:			
a.	Initial Setting Time (minutes)	140	Not less than 30
b.	Final Setting Time (minutes)	240	Not more than 600
Compressive Strength (MPa)			
a.	3 days	25.64	Not less than 16
b.	7 days	35.44	Not less than 22
c.	28 days	52.64	Not less than 33
d.	Drying Shrinkage(%)	0.027	Not more than 0.15
e.	Flyash Addition (%)	29.60	Not more than 35
B. CHEMICAL REQUIREMENTS			
a.	Insoluble Residue (%)	25.93	X+4(100-X)/100; X = % of Flyash
b.	Magnesia (%)	1.03	Not more than 6.0
C.	Sulphuric Anhydride (%)	2.22	Not more than 3.5
d.	Loss on Ignition (%)	2.32	Not more than 5.0
e.	Alkali Content (%)	0.61	Not more than 0.90
i.	Temperature During Testing ⁰ C	27.20	27 ± 2

X

Section In-Charge (Q.C)

CO Part

Authorised Signature