





## **Zuari Cement Ltd**

SOLAPUR GRINDING UNIT SOLAPUR, MAHARASHTRA

## **ENGINEERED FOR DURABILITY**

	TEST CERTIFICATE	Week No	29
	ORDINARY PORTLAND CEMENT 53G	Year	2022
SAMPLE	RESULT OBTAINED	REQUIREMENT	
TEST TYPE	FROM TEST	IS : 269-2015	
PHYSICAL REQUIREMENTS			
. Fineness -Blaine(M²/Kg)	289	Not less than 225 M <sup>2</sup> /Kg	
.Soundness:			
A.Autoclave Expansion (%)	0.056	Not more than 0.8 %	
Le Chatelier Expansion (in mm)	1.00	Not more than 10 mm	
.Setting Time (in minutes)			
A.Initial	160	Not less than 30 minutes	
3.Final	230	Not more than 600 minutes	
.Compressive Strength (MPa)			
1.72 ± 1 hr.(3 days)	35.3	Not Less than 27 MPa	
3.168 ± 2 hr.(7 days)	45.0	Not Less than 37 MPa	
C.672 ± 4 hr.(28 days)	UT	Not Less than 53 MPa	
CHEMICAL REQUIREMENTS			
.Loss on Ignition (% by mass)	1.86	4 % Maximum	
Insoluble Residue (% by mass)	4.80	5 % Maximum	
.Magnesium Oxide (MgO) (% by mass)	1.25	6.0 % Maximum	
Total Sulphur content calculated as (SO3) by mass)	2.78	3.5 % Maximum	
i.Chlorides (% by mass)	0.018	0.10 % Maximum	
Lime Saturation Factor			
<u>Cao - 0.7 So3</u> (2.8 SiO2+ 1.2 AL2O3+0.65Fe2O3)	0.86	0.80 to 1.02	
7.A/F (Al2O3 / Fe2O3)	1.35	0.66 Minimum	
B.Performance Improver Fly Ash (%)	5.00	5.0 % Maximum	
Votes required for pasts of standard consisten	20.50		

Water required for paste of standard consistency (%)

28.50

The above cement complies with the requirements of IS 269: 2015 For ORDINARY PORTLAND CEMENT 53G

Computer generated Report, hence Signature is not required

For BIS certification details see website bis.org.in

For Zuari Cement Ltd MANAGER (QC)